

### Gas Equipment Bulletin: Piped Connections to Manufactured Homes

ITS 21-020

**Rationale:** Guidance for installing acceptable swing joints (as per section 36 of the Gas and Oil Burner Regulation).

When installing a manufactured home connection to a utility meter set, the swing joint required should be a minimum 12 inches (30 cm) above grade, and a minimum of a 12 inches (30 cm) lateral from the building.

Refer to current CSA B149.1-2015 Clause 6.21.8.

**Figure 1**  
**Piped connections to manufactured homes**

